



Since the wall mountingset has two stages, the distances from the wall are indicated in the table below according to the two stages

Product Name	Tube	Height (mm)	Width (mm)	Pipework Center (mm)	Thickness (mm)	Wall to Back (mm)	Wall to Pipe Center (mm)	Wall to Front (mm)
Maple	6	615	488	455	39,5	34,40/43,40	47,30/56,30	73,90/82,90
Maple	9	1000	488	455	39,5	34,40/43,40	47,30/56,30	73,90/82,90
Maple	12	1390	488	455	39,5	34,40/43,40	47,30/56,30	73,90/82,90